

ADDENDUM

Addendum No. 1

Owner: City of Owosso
Project: 2025 Drainage Improvements Project
Engineer: City of Owosso

NOTICE TO ALL PROSPECTIVE BIDDERS

BIDS DUE: November 26, 2024 at 3pm

=====

This Addendum is a part of the Contract Documents and modifies the previously issued Bidding Documents. Acknowledge receipt of this Addendum in the space provided on the "*Signature Page and Legal Status*" section of the Bid Proposal. Failure to do so may result in rejection of the Bid.

ITEM NO. 1:

Add "2025 Drainage Improvements Project Questions" to the Contract Documents.

END OF ITEM NO. 1

END OF ADDENDUM NO. 1

2025 Drainage Improvements Project Questions

Q: For North St, what kind of pipe is the existing 200'?

A: The existing pipe is a corrugated metal pipe.

Q: For North St, is the new ADS pipe being installed perforated with sock or solid pipe?

A: Proposed pipe shall be solid pipe.

Q: For Coventry Ct, does the whole ditch have to be cleaned within the ditch or only the portion with a 10' ROW?

A: The whole ditch shall be cleaned from STA 4+50 (behind 730 Coventry Ct) to STA 16+12 (culvert at railroad crossing).

Q: For both locations, what are we doing with spoils?

A: For Coventry Ct, the spoils can be placed along banks to re-shape the ditch. Any excess spoils shall be removed from the site.

For North St, the spoils shall be removed from the site.