#### Request for Proposal for Mechanical / Electrical Engineering Services

#### City of Owosso City Hall Improvements Project

#### ADDENDUM #2 15 November 2024

Below is a summary of the pre-bid walk-through for the M/E Engineer RFP for the above-mentioned project:

- 1. The group began with introductions of both the Ownership team and the participants.
- 2. Katie then reiterated some of the key milestone dates for the RFP:
  - Questions are due no later than noon on 14 November 2024.
  - Proposals are due by 5:00 pm EST on 20 November 2024.
  - The Ownership team will make a recommendation to the City Council for their approval at the 02 December Council meeting and will inform the teams sometime that week.
- 3. Regarding the project schedule, Nathan shared that the City's fiscal year runs from July to June.

The following questions were received during the walk-through. Answers are captured below.

- 4. It appears that the building is in a floodplain / floodway. Are there any issues foreseen with permitting? *No.*
- Are there any drawings of the building available? Yes, though they are of the original layout, and may not be accurate to today's configuration. These will be shared with the proposing teams.
- 6. Will the interior ductwork be replaced? No, though some of the actuators and dampers will be. To that end, the City recently completed a flow test on the system, and will share the test and balance report with the proposers.
- 7. How does the Historic District Commission play into the scope of work, and what is that process? Nathan noted that there is nothing within the M/E scope that will require their review—no ductwork should be routed along the building façade. He also indicated that any landscaping/fencing re-do around the mechanical units and generator will not need review, since it does not specifically alter or affect the building exterior.
- 8. How long has the unit in the closet adjacent to the Chambers been out of service? Ryan noted that the unit has not been in service since he has been with the City, beginning in 2021.
- 9. What area(s) of the building does (did?) this unit serve? This was a bit unclear and will need further investigation. For what it's worth, an observation was made that the control box in the room is labelled VAV 4 and RTU 1.

10. Does the City want to use JCI for controls, given that this is their current system? Not necessarily. The City wants to upgrade to a new system that is appropriate given new technologies and their specific needs. JCI is acceptable, but not mandated.

As an aside, the group was able to view the two control panels, one in the basement and one on the second floor.

- 11. What alterations do you foresee to the electrical service? The service panel needs to be replaced, though there is some capacity. Ryan noted that the service coming into the building is new from Consumers, but the panel needs updating.
- 12. Will the scope of work be divided among other professionals (ie. an architect)? No. The chosen engineer should hold all required services under their scope of work.
- 13. Will the ductwork leading from the unit on the roof outside of the women's restroom need to be insulated?

Yes. Any outdoor ducts will require insulation.

- 14. What part of the building is serviced by the unit on the roof outside of the women's restroom? *It services the east half of the building.*
- 15. Is the building sprinkled? No, though there is a halon suppression system in the IT room.
- 16. Are there other symptoms in the IT room that need to be addressed (ie. humidity)? No. The City just needs a new unit to serve this space, possibly with some added capacity.
- 17. Is there a receptacle for power outside near the pad? Yes.
- 18. What happens to all of the conduit/piping in the subterranean room beneath the mechanical pad? As stated in the RFP, these will need to be assessed to determine if they are still active, and will need to be addressed as part of the solution to this space.
- 19. How much of the building needs to be tied to the new generator? *The entire building, including all systems / services.*

A few other items were noted during the walk-through, as follows:

- 20. There is currently no back-up power save for a 4-hour battery for the IT systems.
- 21. None of the mechanical units have been modified at least since 2021 (when Ryan joined the City).
- 22. Ryan noted that there is a new electrical service to the building. This was the one on the right when facing the front of the building. It is a 100,000 kW service.

The following questions were received after the walk-through:

- 23. Is the intent to keep the building open during construction? Yes.
- 24. Is the intent to replace all electrical distribution or just those impacted by mechanical and generator upgrades?


This decision will ultimately be based on the budget. We will look to our engineering team to evaluate and make a recommendation on the distribution centers that need to be replaced.


- 25. Do the feeders get replaced with the distribution panels? No, unless it is deemed necessary by the engineering professional.
- 26. CLARIFICATION: As you develop your fee, please clearly outline any assumptions or exclusions to the terms of the RFP.
- 27. The following additional information is included as part of this addendum:
  - Pre-bid walk-through sign-in sheet
  - Existing building drawings
  - Test and balance report
  - Structural assessment
  - Mechanical data plate photos
  - Generator data plate photo
  - Miscellaneous project photos


end of Addendum #2


### Sign-in Sheet


Name	Company	E-mail Address
Jacob Landrey Nathan Smith Renee Ladomer SEAN TANACSLO Nich Hill Eric Schippers Robert WERBROUCH	Spice Group Matrix Consulting Fishbeck Olim Advisors Tetto Tech Century AtE IGNYTE DESIM	jacob. Undrey @ spicegroup.com NSmith@matrixCeinc.com <u>RLadomer@Fuhbeck.com</u> <u>Sean.Tebacsho.@ohm-ad</u> <u>nick.hill1@tettatech.com</u> <u>eschippers@centuryae.com</u> <u>RWFRBROUCIC@IGNYTE.DESIGN</u> <u>icom</u>
	TETRA TECH Nick Hill, P.E., LE Mech 1136 Oak Valley Drive, Suite 100, Ann Arbo	hanical Engineer
	1136 Oak Valley Drive, Suite 100, Ann Aroc Tel +1.734.213.4016 Cell nick.hill1@tetratech.com   ww	+1.847.863.8053
	2	














Independent TAB Services NEBB Certification # 3486

4221 East Baldwin Road - Holly, MI 48442 (810) 579-5000 FAX: (810) 579-2664

Owosso City Hall Pre-demo Readings

Owosso, Michigan



Date: 2/13/2024 Test and Balance Report

#### Summary of Balancing Reports NEBB Certification Number: 3486

Project:	Owosso City Hall								
Location: 301 West Main st. Owosso, MI 48867									
Engineer:									
Contractor:	William E. Walter	Date:	02/13/24						
Tests were evaluated by:	Lee Marshall	Job No:	1523-24						
Tests were performed by:	Mickey Denver								
Index # System Description									
# 1 RTU Second Flo									
	East Supply								
	West Supply								
4 RTU Basement S									
	or IT Room Supply								
6									
7									
8									
9									
10									
11									
12									
13									
14									
15									
16									
17									
18									
19									
20									
21									
22									
23									
24									
25									
26									
27									
28									

NEBB Certification #3486

### Air Apparatus Test Report

**Project:** 

Owosso City Hall

Unit Number: RTU

Area Served:


Second Floor Supply

Fan / Unit Data								
Make	Tra	ane						
Model	YCD120	B4HAEB						
Type / Size	~ ~							
Class/Arrangement	~ ~							
Serial Number	P42103977D							
Discharge	~							
Fan Drive	e Informatio	n						
Sheave Diameter	BK	(85						
Shaft Size(Bushing)	1"							
No. Belts/Size	1 BX62							

Test Data	Desig	gn	Α	ctual		
Total CFM	2			1676		
Return Air CFM	2			1500		
Minimum OA CFM	2			176		
Total S.P.	2		1	.415"		
External S.P.	1		1	1.150"		
Fan RPM	~			885		
Brake Horsepower	2	~		1.93		
Electrica	al Test D	)ata				
Motor Amps T1 T2 T3	2.70	2.	80	2.80		
Motor Volts T1 T2 T3	500	49	97 497			
V.F.D. Setting	~					
Motor Frequency	~					
Thermal Overloads	Therr	nally	Prot	ected		

Motor Data										
Manufacturer		Mara	athon							
H.P. / Amps	2.00			3.1						
Ph./Hertz/Volts	3	6	0	460						
Frame / RPM	56HZ-80 1725									
Ser. Factor/P. F.	1.15 ~									
Efficiency:	~									
Motor Driv	ve Inforn	nati	on							
Sheave Diameter	ŀ	\K45	Fixe	d						
Shaft Size (Bushing)	7/8"									
CL to CL Distance	21-1/2"									
Motor Adjustment	+ 0		-	0						

Test Data	Design	Actual
Fan Discharge S.P.	~	+1.090"
Fan Suction S.P.	~	+0.325"
Total S.P.	~	+1.415"
Component	Pressure D	rops
Filter:	~	0.041"
Coil:	~	0.143"
HTX:	~	0.080"
Test C	Conditions	
Return Air Damper	~	~
Outside Air Damper	~	~
Relief Air Damper	~	~



NEBB Certification #3486

### Duct Traverse Test Report

Project:	Owosso City Hall		RTU
Area Served:	Second Floor Supply	Location:	Roof

Traverse Description:		Minimum Outdoor Air Data											
	Width	n He	ight	Design (	CFM	Desigr	n FPM		Achiev	ed FPM	A	Achieved CFM	
Duct Size:	42	1	2	~		-			5	6		176	
Square Ft.:	3.1	50						D	).S.P. @	Readir	ng		
Reading Description:		Alt. in Ft @ Reading		Alt. in Ft @ Reading		1 ~	Τe	Temp. @ Reading (Deg.		eg. F)		~	
Position	1	2	3	4	5	6	7	7	8	9	10	11	12
1	32	60	76										
2													
3													
4													
5													

Traverse Description:														
	Width	n He	ight	Design (	CFM	Design FPM		PM	Achiev	ed FPM	A	Achieved CFM		
Duct Size:	2		~	~			~			~		~		
Square Ft.:		~						D.S.P. @ Reading			~			
Reading Description:			Alt. ir	n Ft @ Re	eading	g	۲	Tem	o. @ Rea	ading (D	eg. F)		~	
Position	1	2	3	4	5		6	7	8	9	10	11	12	
1														
2														
3														
4														
5														

Remarks/Schematics:		
	Index:	1
	Page:	1
	Date:	2/13/2024

NEBB Certification #3486

### **Outlet/Inlet Test Report**

Project:

Owosso City Hall

Unit Number: RTU

Area Served:

Second Floor Supply

Area Carried		Outlet/Inlet		Des	ign	Т	est Da	ta	Tes	st Res	ults
Area Served	NO.	Size/Type	AK	CFM	VEL	1st	2nd	3rd	VEL	DP	CFM
		Supply Air Data									<u> </u>
	1	6''Ø Nk Diff	FH	~		0					0
	2	6''Ø Nk Diff	FH	~		36					36
	3	6''Ø Nk Diff	FH	~		29					29
	4	6''Ø Nk Diff	FH	~		0					0
	5	6''Ø Nk Diff	FH	~		0					0
	6	6''Ø Nk Diff	FH	~		38					38
	7	8''Ø Nk Diff	FH	~		47					47
	8	8''Ø Nk Diff	FH	~		39					39
	9	16"x8" Reg	FH	~		204					204
	10	6''Ø Nk Diff	FH	~		35					35
	11	6''Ø Nk Diff	FH	~		51					51
	12	6''Ø Nk Diff	FH	~		0					0
	13	6''Ø Nk Diff	FH	~		29					29
	14	6''Ø Nk Diff	FH	~		40					40
	15	8''Ø Nk Diff	FH	~		47					47
	16	24"x12" Open	FH	~		310					310
	17	6''Ø Nk Diff	FH	~		65					65
	18	6''Ø Nk Diff	FH	~		90					90
	19	8''Ø Nk Diff	FH	~		80					80
	20	8''Ø Nk Diff	FH	~		121					121
	21	8''Ø Nk Diff	FH	~		161					161
	22	10"Ø Nk Diff	FH	~		39					39
	23	8''Ø Nk Diff	FH	~		138					138
	24	8''Ø Nk Diff	FH	~		77					77
											1
		Design Capacity		~			A	chieved	I Capacit	v	1676
											1
											<u> </u>
											<u> </u>
											1
											1
											1
											<u> </u>
											<u> </u>
			1								1
											<u></u>
arks/Schematics:											
arks/Schematics:								Г	Index:		1
arks/Schematics:								F	Index: Page:		1 3

NEBB Certification #3486

### Air Apparatus Test Report

**Project:** 

Owosso City Hall

Unit Number: RTU

Area Served:


First Floor East

Fan / Unit Data								
Make	Tra	ane						
Model	YCH060	C4H0BF						
Type / Size	~ ~							
Class/Arrangement	~	~						
Serial Number	3258D							
Discharge		~						
Fan Drive	e Informatio	n						
Sheave Diameter								
Shaft Size(Bushing)								
No. Belts/Size								

Test Data	Desig	gn	Actual		
Total CFM	2		1464		
Return Air CFM	2			1315	
Minimum OA CFM	2			149	
Total S.P.	2		C	).608"	
External S.P.	1		0.477"		
Fan RPM	1		1630		
Brake Horsepower	2		0.39		
Electrica	al Test D	Data			
Motor Amps T1 T2 T3	~	1.50		~	
Motor Volts T1 T2 T3	~	49	99	~	
V.F.D. Setting	~				
Motor Frequency	~				
Thermal Overloads	Thern	nally	Prote	ected	

Motor Data								
Manufacturer			~					
H.P. / Amps	0.60			2.5				
Ph./Hertz/Volts	1 60 460							
Frame / RPM	2	~ ~						
Ser. Factor/P. F.	~ ~							
Efficiency:			~					
Motor Driv	ve Inforn	nati	on					
Sheave Diameter								
Shaft Size (Bushing)	Direct Drive							
CL to CL Distance	Direct Drive							
Motor Adjustment								

Test Data	Design	Actual						
Fan Discharge S.P.	~	+0.297"						
Fan Suction S.P.	~	+0.311"						
Total S.P.	~	+0.608"						
Component Pressure Drops								
Filter:	1	None						
Coil:	~	0.092"						
HTX:	~	0.039"						
Test C	Conditions							
Return Air Damper	~	~						
Outside Air Damper	~	~						
Relief Air Damper	~	~						



NEBB Certification #3486

### Duct Traverse Test Report

Project:	Owosso City Hall	Unit Number:	RTU
Area Served:	First Floor East	Location:	Roof

Traverse Description:		Minimum Outdoor Air Data											
	Width	n He	ight	ight Design CFM Design		gn F	PM	PM Achieved FPM			Achieved CFM		
Duct Size:	40	1	2 ~		~			50			149		
Square Ft.:	3.0	3.000		D.S.		D.S.P. @ Reading		ig					
Reading Description:		Alt.		Alt. in Ft @ Reading			,	Tem	emp. @ Reading (Deg		eg. F)	F) ~	
Position	1	2	3	4	5	6	6	7	8	9	10	11	12
1	61	38	50										
2													
3													
4													
5													

Traverse Description:													
	Width	n He	ight	Design (	CFM	Design FPM		PM	Achieved FPM		A	Achieved CFM	
Duct Size:	~		~	~ ~		~			~			~	
Square Ft.:	~		D.\$		D.S.P. @ Reading				~				
Reading Description:				Alt. in Ft @ Reading		g	۲	Tem	Temp. @ Reading (Deg		eg. F)		~
Position	1	2	3	4	5		6	7	8	9	10	11	12
1													
2													
3													
4													
5													

Remarks/Schematics:		
	Index:	2
	Page:	2
	Date:	2/13/2024

NEBB Certification #3486

### **Outlet/Inlet Test Report**

Owosso City Hall

Unit Number: RTU

Area Served:

First Floor East

Area Served	Outlet/Inlet		Des	sign	Т	est Da	ta	Test Results			
Area Serveu	NO.	Size/Type	AK	CFM	VEL	1st	2nd	3rd	VEL	DP	CFM
		Supply Air Data									
	1	10"x6" Reg.	FH	~		65					65
	2	10"x6" Reg.	FH	~		153					153
	3	6''Ø Nk Diff	FH	~		65					65
	4	8''Ø Nk Diff	FH	~		234					234
	5	12"x10" Reg.	FH	~		82					82
	6	16"x8" Reg	FH	~		63					63
	7	14"x8" Open	FH	~		70					70
	8	8''Ø Nk Diff	FH	~		103					103
	9	8''Ø Nk Diff	FH	~		109					109
	10	8''Ø Nk Diff	FH	~		53					53
	11	8''Ø Nk Diff	FH	~		30					30
	12	8''Ø Nk Diff	FH	~		90					90
	13	8''Ø Nk Diff	FH	~		120					120
	14	8''Ø Nk Diff	FH	~		86					86
	15	8''Ø Nk Diff	FH	~		141			<b> </b>		141
				ļ							
		Design Capacity		~			4	chieve	d Capaci	ty	1464
									∥		
									∥		
	_								∥		
									∥		
									∥		
									<b> </b>		
									∦		
	_								∦		
	_								∦		
	_								∦		
	_								╢────		
	_								╢────		
	_								╢────		
	_								╢────		
	_								╢────		
									┨────		
arks/Schematics:											
								E	Index:		2
									Page:		3
									Date:	2/1	3/2024

NEBB Certification #3486

### Air Apparatus Test Report

**Project:** 

Owosso City Hall

Unit Number: RTU

Area Served:

First Floor West


Location: Ground

Fan / Unit Data								
Make	Tra	ane						
Model	YCH060	C4H0BF						
Type / Size	~ ~							
Class/Arrangement	~	~						
Serial Number	P41103200D							
Discharge		~						
Fan Drive	e Informatio	n						
Sheave Diameter								
Shaft Size(Bushing)	Direct Drive							
No. Belts/Size	1							

Test Data	Desi	gn	Actual		
Total CFM	~		1402		
Return Air CFM	~			1262	
Minimum OA CFM	~			140	
Total S.P.	~		(	).701"	
External S.P.	2		0.637"		
Fan RPM	~		1624		
Brake Horsepower	~		0.18		
Electrica	al Test D	)ata			
Motor Amps T1 T2 T3	~	0.70		~	
Motor Volts T1 T2 T3	~	49	97 ~		
V.F.D. Setting	~				
Motor Frequency	~				
Thermal Overloads	Thern	nally	Prot	ected	

Motor Data								
Manufacturer	~							
H.P. / Amps	0.60 2.5							
Ph./Hertz/Volts	1	6	0	460				
Frame / RPM	~ ~							
Ser. Factor/P. F.	~ ~							
Efficiency:			~					
Motor Driv	ve Inforn	nati	on					
Sheave Diameter								
Shaft Size (Bushing)	Direct Drive							
CL to CL Distance	Direct Drive							
Motor Adjustment								

Test Data	Design	Actual
Fan Discharge S.P.	~	+0.394"
Fan Suction S.P.	~	+0.307"
Total S.P.	~	+0.701"
Component	Bracquira D	2000
	Flessule D	ops
Filter:	~	0.087"
Coil:	1	0.038"
HTX:	1	0.061"
Test C	Conditions	
Return Air Damper	~	~
Outside Air Damper	~	~
Relief Air Damper	~	~



NEBB Certification #3486

### Duct Traverse Test Report

Project:	Owosso City Hall	Unit Number:	RTU
Area Served:	First Floor West	Location:	Roof

Traverse Description:		Minimum Outdoor Air Data											
	Width	n He	ight	ight Design CFM Design FF			PM Achieved FPM			Ad	Achieved CFM		
Duct Size:	40	1	2	~			~		4	7		140	
Square Ft.:	3.0	000							D.S.P. @	Readin	g		
Reading Description:			Alt. in Ft @ Reading		<b>j</b>	~ Temp. @ Readi		ading (Deg. F)		•	•		
Position	1	2	3	4	5		6	7	8	9	10	11	12
1	25	36	79										
2													
3													
4													
5													

Traverse Description:													
	Width	He	ight	Design (	CFM	D	esign F	PM	Achiev	ed FPM	Ad	chieved	CFM
Duct Size:	۲		~	~			~			~		~	
Square Ft.:	-	-							D.S.P. @	Readin	g		~
Reading Description:			Alt. in	Ft @ Re	eading	g	~	Tem	o. @ Rea	ading (D	eg. F)		~
Position	1	2	3	4	5		6	7	8	9	10	11	12
1													
2													
3													
4													
5													

Remarks/Schematics:		
	Index:	3
	Page:	2
	Date:	2/13/2024

NEBB Certification #3486

### Outlet/Inlet Test Report

Project:	Owosso City Hall

Unit Number: RTU

Area Served:

First Floor West

Area Served		Outlet/Inlet		Des	sign	Test Data			Tes	st Res	sults	
Area Served	NO.	Size/Type	AK	CFM	VEL	1st	2nd	3rd	VEL	DP	CFM	
		Supply Air Data										
	1	8''Ø Nk Diff	FH	~		36					36	
	2	8''Ø Nk Diff	FH	~		162					162	
	3	6''Ø Nk Diff	FH	~		29					29	
	4	6''Ø Nk Diff	FH	~		0					0	
	5	8''Ø Nk Diff	FH	~		181					181	
	6	8''Ø Nk Diff	FH	~		144					144	
	7	8''Ø Nk Diff	FH	~		161					161	
	8	10"x6" Reg.	FH	~		41					41	
	9	12"x10" Reg.	FH	~		139					139	
	10	8''Ø Nk Diff	FH	~		35					35	
	11	8''Ø Nk Diff	FH	~		38					38	
	12	12"x10" Reg.	FH	~		213					213	
	13	8''Ø Nk Diff	FH	~		142					142	
	14	6''Ø Nk Diff	FH	~		81					81	
		Design Capacity	•	~			A .	chieve	d Capaci	y	1402	
emarks/Schematics:												
									Index:		3	
									Page:		3	
									Date:		3/2024	

NEBB Certification #3486

### Air Apparatus Test Report

**Project:** 

Owosso City Hall

Unit Number: RTU

Area Served:

Basement


Location: Ground

Fan / Unit Data						
Make	Tra	ane				
Model	YCH120	B4H0EB				
Type / Size	~ ~					
Class/Arrangement	~	~				
Serial Number	P43102206D					
Discharge	~					
Fan Drive	e Informatio	n				
Sheave Diameter	Bk	(72				
Shaft Size(Bushing)	1"					
No. Belts/Size	1	BX62				

Test Data	Desi	gn	Α	ctual	
Total CFM	2			3683	
Return Air CFM	2			3589	
Minimum OA CFM	2			94	
Total S.P.	2		1	.357"	
External S.P.	~		(	).915"	
Fan RPM	~			808	
Brake Horsepower	~		3.33		
Electrica	al Test D	)ata			
Motor Amps T1 T2 T3	4.70	4.	60	4.80	
Motor Volts T1 T2 T3	497	50	D1	499	
V.F.D. Setting	~				
Motor Frequency	~				
Thermal Overloads	Therr	nally	Prot	ected	

Motor Data							
Manufacturer	(	GE M	lotors				
H.P. / Amps	3.00			4.6			
Ph./Hertz/Volts	3	6	0	460			
Frame / RPM	56HZ			1725			
Ser. Factor/P. F.	~			1			
Efficiency:			,				
Motor Driv	ve Inforr	nati	on				
Sheave Diameter	8	450L	at M	in			
Shaft Size (Bushing)	7/8"						
CL to CL Distance	22"						
Motor Adjustment	+ 0		-	0			

Test Data	Design	Actual							
Fan Discharge S.P.	~	+0.477"							
Fan Suction S.P.	~	+0.880"							
Total S.P.	~	+1.357"							
Component	Pressure D	rops							
Filter:	1	0.175"							
Coil:	1	0.195"							
HTX:	~	0.072"							
Test Conditions									
Return Air Damper	~	~							
Outside Air Damper	~	~							
Relief Air Damper	~	~							



NEBB Certification #3486

### Duct Traverse Test Report

Project:	Owosso City Hall	Unit Number:	RTU
Area Served:	Basement	Location:	Ground

Minimum Outdoor Air Data Traverse Description: Design CFM Design FPM Achieved FPM Achieved CFM Width Height Duct Size: 34 12 37 94 ~ ~ D.S.P. @ Reading 2.550 Square Ft.: Reading Description: Alt. in Ft @ Reading Temp. @ Reading (Deg. F) ~ ~ Position 2 9 12 1 3 4 5 6 7 8 10 11 28 40 42 1 2 3 4 5

Traverse Description:													
	Width	n He	ight	Design (	CFM	D	esign F	PM	Achiev	ed FPM	A	chieved	CFM
Duct Size:	~		~	~			2			~		~	
Square Ft.:		~		D.S.P. @ Reading		D.S.P. @ Reading				~			
Reading Description:			Alt. in	Ft @ R	eading	J	۲	Tem	Temp. @ Reading (Deg. F)		(Deg. F) ~		~
Position	1	2	3	4	5		6	7	8	9	10	11	12
1													
2													
3													
4													
5													

Remarks/Schematics:		
	Index:	4
	Page:	2
	Date:	2/13/2024

NEBB Certification #3486

### **Outlet/Inlet Test Report**

Project:	Owosso City Hall	Unit Num
		_

Area Served:

First Floor East

nber: RTU

Anos Comused	I	Outlet/Inlet		Des	sign	Т	est Da	ta	Tes	st Res	ults
Area Served	NO.	Size/Type	AK	CFM	VEL	1st	2nd	3rd	VEL	DP	CFM
		Supply Air Data									
	1	20"x12" Open	FH	~		1973					1973
	2	8''Ø Nk Diff	FH	~		138					138
	3	8''Ø Nk Diff	FH	~		0					0
	4	8''Ø Nk Diff	FH	~		155					155
	5	6''Ø Nk Diff	FH	~		37					37
	6	10"x4" Reg.	FH	~		37					37
	7	10"x6" Reg.	FH	~		39					39
	8	8''Ø Nk Diff	FH	~		47					47
	9	10''Ø Nk Diff	FH	~		95					95
	10	6''Ø Nk Diff	FH	~		54					54
	11	8''Ø Nk Diff	FH	~		137					137
	12	10"x6" Reg.	FH	~		170					170
	13	8''Ø Nk Diff	FH	~		249					249
	14	6''Ø Nk Diff	FH	~		149					149
	15	10"x6" reg.	FH	~		96					96
	16	8''Ø Nk Diff	FH	~		53					53
	17	8''Ø Nk Diff	FH	~		65					65
	18	6''Ø Nk Diff	FH	~		49					49
	19	6''Ø Nk Diff	FH	~		51					51
	20	6''Ø Nk Diff	FH	~		27					27
	21	6''Ø Nk Diff	FH	~		32					32
	22	6''Ø Nk Diff	FH	~		30					30
	23	6''Ø Nk Diff	FH	~		0					0
		Design Capacity		~			4	chieved	l Capacit	y	3683
	_										
	_										
	_										
	╢────								∥		<b></b>
	╢────					L					$\parallel$
Remarks/Schematics:											
								Γ	Index:		4
									Page:		3
									Date:	2/1	3/2024

NEBB Certification #3486

### Air Apparatus Test Report

**Project:** 

Owosso City Hall

Unit Number: Furnace

Area Served:

Second Floor IT Room


Location: Above Ceiling

Fan / Unit Data							
Make	Bry	/ant					
Model	376CAV04	8096AGJA					
Type / Size	~ ~						
Class/Arrangement	~ ~						
Serial Number	3099A20312						
Discharge		~					
Fan Drive	e Informatio	n					
Sheave Diameter							
Shaft Size(Bushing)	Direct	t Drive					
No. Belts/Size	1						

Test Data	Desi	gn	Actual		
Total CFM	2			1163	
Return Air CFM	2			1163	
Minimum OA CFM	2			~	
Total S.P.	2		0	).565"	
External S.P.	1		C	).464"	
Fan RPM	~		~		
Brake Horsepower	~			0.19	
Electrica	al Test D	)ata			
Motor Amps T1 T2 T3	~	3.	60	~	
Motor Volts T1 T2 T3	~	12	26	~	
V.F.D. Setting	~				
Motor Frequency	~				
Thermal Overloads	Therr	nally	Prot	ected	

Mot	or Data	a				
Manufacturer			,			
H.P. / Amps	0.50			10.2		
Ph./Hertz/Volts	1	6	0	115		
Frame / RPM	~			~		
Ser. Factor/P. F.	~ ~					
Efficiency:	~					
Motor Driv	ve Inforn	nati	on			
Sheave Diameter						
Shaft Size (Bushing)	Direct Drive					
CL to CL Distance	Direct Drive					
Motor Adjustment						

Test Data	Design	Actual					
Fan Discharge S.P.	~	+0.384"					
Fan Suction S.P.	~	+0.181"					
Total S.P.	~	+0.565"					
Component Pressure Drops							
Filter:	1	.101"					
Coil:	1	~					
HTX:	~	~					
Test C	Conditions						
Return Air Damper	~	100%					
Outside Air Damper	~	~					
Relief Air Damper	~	~					



NEBB Certification #3486

### Outlet/Inlet Test Report

Project:

Owosso City Hall


Unit Number: Furnace


Area Served:


Second Floor IT Room Supply

Location: Above Ceiling

Area Served		Outlet/Inlet		Des	sign	Т	Test Data		Test Result		
Area Served	NO.	Size/Type	AK	CFM	VEL	1st	2nd	3rd	VEL	DP	CFM
		Supply Air Data									
	1	6" Open	FH	~		36					36
	2	6''Ø Nk Diff	FH	~		131					131
	3	12"Ø Nk Diff	FH	~		581					581
	4	6''Ø Nk Diff	FH	~		132					132
	5	6''Ø Nk Diff	FH	~		180					180
	6	6''Ø Nk Diff	FH	~		103					103
		Design Capacity		~			ļ A	chieve	d Capacit	y	1163
				┃							
				┃							
				┃					ļ		
											-
				∥							-
				<b> </b>							-
				∦					·		-
				∦							
				╽────							•
				∦							
				∦					· · · · · · · · · · · · · · · · · · ·		-
narks/Schematics:											
								Г	Index:		5
									Page:		2
									Date:	2/1	3/2024







#### MEMORANDUM


# $\mathbf{O}$

To:	Glenn M. Chinavare – Director of Public Services			
	City of Owosso, Michigan			
Subject:	Basement Storage Room – Structural Evaluation			
From:	Aaron J Davenport, PE	Date:	April 3, 2020	

#### Introduction

Jon P. Nassaux, PE and Aaron J. Davenport, PE of Jones & Henry Engineers, Ltd visited the Owosso City Hall on March 16, 2020, to review the structural condition of the basement storage room. In the past the storage room served as a coal storage room and was constructed with cast-in-place concrete walls and cast-in-place concrete ceiling/roof. The roof is supported by four integral concrete beams. The roof supports two exterior HVAC units and a standby generator. The review included a visual inspection of the physical condition of concrete walls, roof slab and roof beams.

Prior to the inspection, maintenance personnel informed us that the room has been leaking water for some time. During the inspection, it was discovered that the roof slab was cracked and spalling concrete in several locations, exposing reinforcing bars.



### Jones & Henry Engineers, Ltd.

City of Owosso, Michigan Basement Storage Room – Structural Evaluation

Three of the four beams were cracked. Two of the beams were severely cracked to the point that they could not be repaired by patching or epoxy injection. These beams are damaged to the extent that they no longer have any structural viability.



It was evident that, over time, water has migrated into the concrete cracks and corroded the reinforcing within. Eventually the reinforcement corrosion expanded and increased the cracks widths to a degree that repair is not practical.

The walls of the room were sounded with a hammer and determined to be sound concrete. The walls are in good enough structural condition for continued use. The extent of the damage to the roof beams is such that the beams should be shored as soon as possible to protect personnel and the equipment above.

#### **Restoration Options**

After reviewing the plans and physical condition, we propose the following two (2) methods of restoring the structural viability:

### Jones & Henry Engineers, Ltd.

City of Owosso, Michigan Basement Storage Room – Structural Evaluation

#### Option 1:

Summary: Option 1 would provide adequate structural support for the equipment sitting above the coal room. This option would require that the storage area below be infilled with a lightweight structural fill to support the existing concrete slab. This option will support the roof beams, slab and the HVAC equipment above with the least amount of effort and expense, however the storage capacity of the room will be lost.

#### Work Items

- Shore roof beams to support HVAC units during construction.
- Masonry Block infill of the existing door entrance way to the storage area.
- Core holes through the existing roof slab at several locations.
- Place light weight flowable concrete through roof holes to entirely fill the storage space below.
  - Note This will need to be installed in three lifts, 24-hours apart, to reduce lateral pressure on block infill at the doorway and existing walls

#### Estimated construction cost \$43,000

#### Option 2:

Summary: Option 2 maintains the storage area's functionality and provides a structurally sound support for the existing HVAC units and generator above. This option comes at a higher cost and has a longer construction period but will allow for the continued use of the space and will extend the useful life of this portion of City Hall.

#### Work Items

- Shore roof beams to support HVAC units during removal.
- Shore walls to support lateral soil loads while roof is removed.
- Remove HVAC units, generator, and associated equipment, piping, wiring, and ducts.
- Remove roof slab and beams.
- Install waterstop along the top perimeter of the walls.
- Seal any wall cracks that may allow leakage of water.
- Install new reinforced, cast-in-place concrete roof and equipment pads.
- Reinstall HVAC and generator equipment.

#### Estimated construction cost \$57,000.

### Jones & Henry Engineers, Ltd.

City of Owosso, Michigan Basement Storage Room – Structural Evaluation

Attachments: Engineer's Opinion of Probable Cost – Option 1 and Option 2

Cc: Jon Nassaux, PE – Jones & Henry Engineers, Ltd.

#### ENGINEER'S ESTIMATE OF CONSTRUCTION COST

Jones & Henry Engineers, Ltd. 4791 Campus Drive Kalamazoo, Michigan 49008

Phone (269)-353-9650

Client:	City of Owosso			Project Number:	012-7677.001
Project Name:	<b>City Hall - Basement Storage Area Structural Assess</b>	ment	•	Date:	4/3/2020
Project Location:	Owosso, Michigan		•	Estimator/Engineer:	JPN
				Checked By:	AJD
Type of Work:	Option 1			Stage: [ ] Conceptua	al [ ] Preliminary [X] Final
Item		Estimated		Unit	
No.	Description	Quantity	Unit	Price	Amount
1	General Conditions	10	%	\$3,426.00	\$3,426.00
2	Beam Shoring, Permanent	6	EA	\$200.00	\$1,200.00
3	Door Infill - Block	28	SF	\$45.00	\$1,260.00
4	Roof Slab Coring	6	EA	\$50.00	\$300.00
5	Flowable Fill (Assumes 3 Lifts - 1 per day)	80	CY	\$393.75	\$31,500.00
				Sub Total	\$37,686.00
			C	ontingencies (15%)	\$5,652.90
			То	tal Project Cost:	\$43,338.90

#### Fax (269)-353-9651

#### ENGINEER'S ESTIMATE OF CONSTRUCTION COST

Jones & Henry Engineers, Ltd. 4791 Campus Drive Kalamazoo, Michigan 49008

Phone (269)-353-9650

Fax (269)-353-9651

Client:	City of Owosso			Project Number:	012-7677.001
Project Name:	City Hall - Basement Storage Area Structural Assessmer	nt		Date:	4/3/2020
Project Location:	Owosso, Michigan			Estimator/Engineer:	JPN
				Checked By:	AJD
Type of Work:	Option 2			Stage: [ ] Conceptua	al [ ] Preliminary [X] Final
Item		Estimated		Unit	
No.	Description	Quantity	Unit	Price	Amount
1	General Conditions	10	%	\$4,483.90	\$4,483.90
2	Slab Shoring, Temporary	6	EA	\$200.00	\$1,200.00
3	HVAC Equipment Removal	1	LS	\$4,200.00	\$4,200.00
4	Generator Removal	1	LS	\$2,500.00	\$2,500.00
5	Fencing Removal	66	LF	\$9.00	\$594.00
6	Wall Shoring, Temporary	4	EA	\$200.00	\$800.00
7	Equipment Pad Removal	103	CF	\$30.00	\$3,090.00
8	Ceiling Slab, Remove and Dispose	153	CF	\$45.00	\$6,885.00
9	Saw Cutting, Slab	100	LF	\$6.50	\$650.00
10	Waterstop	76	LF	\$5.00	\$380.00
11	Install Dowels	76	EA	\$36.00	\$2,736.00
12	Cast-In-Place Concrete Slab	8	CY	\$650.00	\$5,200.00
13	Cast-In-Place Equipment Pads	4	CY	\$315.00	\$1,260.00
14	Install Fencing	66	LF	\$9.00	\$594.00
15	HVAC Equipment, Installation	1	LS	\$8,500.00	\$8,500.00
16	Generator, Installation	1	LS	\$5,250.00	\$5,250.00
17	Damp Proofing	1	LS	\$1,000.00	\$1,000.00
				Sub Total	\$49,322.90
			C	ontingencies (15%)	\$7,398.44
			То	tal Project Cost:	\$56,721.34